BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT39894

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/22/2019-20, Date: 20.01.2020

Providing pump motors and PVC pipe lines in ward no. 5 surrounding area Byatarayanapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of "NATARAJ T" ( )		
				In Figures		In Words
1	3	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings For Motor 12.5HP 25 Stage XLI, SL No.35	No	55849.86	167549.58	Rupees Fifty Five Thousand Eight Hundred Forty Nine and Eighty Six Paise Only
2	3	For Motor 15 HP 30 Stage XLII, SL NO. 43	No	62863.02	188589.06	Rupees Sixty Two Thousand Eight Hundred Sixty Three and Two Paise Only
3	3	17.5HP 30 Stage	No	71404.74	214214.22	Rupees Seventy One Thousand Four Hundred Four and Seventy Four Paise Only
4	3	20hP 40 Stage	No	89689.05	269067.15	Rupees Eighty Nine Thousand Six Hundred Eighty Nine and Five Paise Only
5	20	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above Up to 20HP with star delta starter (MR) Page No. XLVII, Sl NO. 13, PWD SR 2018-19	No	20790.0	415800.00	Rupees Twenty Thousand Seven Hundred Ninety Only
6	1850	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings) 50mm dia GI pipe B Class (SR 18-19 PWD, P.No.XLVII Sl.no. 1	Rmtr	410.85	760072.50	Rupees Four Hundred Ten and Eighty Five Paise Only
7	308.33	Supply and fixing Collar for GI Pipes 50MM (Page No. XLVII, Sl NO.2, PWD SR-2018-19	No	178.2	54944.41	Rupees One Hundred Seventy Eight and Twenty Paise Only
8	2500	Supplying of submersible pump cable 1X3X6..0 Sq.mm (Page No. XLVII, Sl NO. 8, PWD SR-2018-19	Mtr	142.56	356400.00	Rupees One Hundred Forty Two and Fifty Six Paise Only

Signature of the contractor

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of "NATARAJ T" ( )		
				In Figures		In Words
9	50	Supplying and fixing MCB (P.NO - XLVII, SL.NO - 19, PWD SR 18-19)	No	891.0	44550.00	Rupees Eight Hundred Ninety One Only
10	1350	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 6, I.NO - 2.3, PWD SR 18-19)	Cum	313.77	423589.50	Rupees Three Hundred Thirteen and Seventy Seven Paise Only
11	3000	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 18-19)	Mtr	390.38	1171140.00	Rupees Three Hundred Ninety and Thirty Eight Paise Only
12	1350	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 7, I.NO - 2.11, PWD SR 18-19)	Cum	126.98	171423.00	Rupees One Hundred Twenty Six and Ninety Eight Paise Only
13	440000	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14)	Sqm	0.34	149600.00	and Thirty Four Paise Only
14	150	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3b KPWD Electrical SR 2010-11	No	148.5	22275.00	Rupees One Hundred Forty Eight and Fifty Paise Only
15	250	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554) (P.NO - 553, I.NO - 10 (d), BWSSB SR 13-14)	Mtr	168.25	42062.50	Rupees One Hundred Sixty Eight and Twenty Five Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

28/02

28/02